ಕಡತದ ಸಂಖ್ಯೆ: ಮು/.../.../.../...

ಪಂಕ್ತಿಯ ಸಂಖ್ಯೆ	ಟಿಪ್ಪಣಿಗಳು ಮತ್ತು ಆಜ್ಞೆಗಳು

ಮು 3/8/16.

(1) ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು (ಮಲಪು) ರವರಿಗೆ ಮಂಡಿಸಿದೆ.

ವಿಷಯ: ಡಾಟಾ ರೇಟ್ ಅನುಮೋದಿಸುವ ಬಗ್ಗೆ.

(2) ಮೇಲ್ಕಂಡ ವಿಷಯಕ್ಕೆ ಸಂಬಂಧಿಸಿದಂತೆ ಈ ಕೆಳಕಂಡ ವಿಶಿಷ್ಟ ವಿವರಣೆಗೆ ಬೆಂಗಳೂರು ವೃತ್ತ ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆಯ ದರಪಟ್ಟಿಯಲ್ಲಿ ದರಗಳು ಲಭ್ಯವಿಲ್ಲದ ಕಾರಣ ಡೆಟಾ ದರಗಳನ್ನು ತಯಾರಿಸಲಾಗಿರುತ್ತದೆ.

Sl.No	Description	Rate
1	Providing and Laying Precast Drain cover slabs of 250mm thickness for drain in Cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including fofrm work, lift charges curing and concrete finished surface on both side etc ., complete as per drawing and direction engineer in charge of work.	5111.00 persqm
2	Providing and Laying Precast Drain cover slabs of 100mm thickness for drain in Cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges curing and concrete finished surface on both side etc., complete as per drawing and direction engineer in charge of work.	1834.00 perSqm
3	Providing and constructing granite/ trap/ basalt size stone masonry (with available stones in foundation) with cement mortar 1:6 stone hammered dressed in courses not less than 20 cms high bound stone at 2mtr apart in each course including cost of materials, labour, curing complete as per specification.	2709.72 perunit(M3)
4	Provding and filling dust in foundation upto plinth required depth for sub soil treatment including watering raming with all lead and lift, complete as per specification.	1182.00 per Cum

(3) ಮುಂದುವರೆದಂತೆ, ಡೆಟಾ ದರಗಳ ಪ್ರತಿಯನ್ನು ಈ ಕಡತದೊಂದಿಗೆ ಲಗತ್ತಿಸಿ, ಸದರಿ ಡೇಟಾ ದರಗಳಿಗೆ ಅನುಮೋದನೆ ಮಾಡಿಕೊಡಲು ಕಡತವನ್ನು ಮುಂದಿನ ಆದೇಶ ಕೋರಿ ಮಂಡಿಸಿದೆ.

(4)

ಮುಖ್ಯ ಅಭಿಯಂತರರು (ಮಲಪು)

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ. ಪು.ತಿ.ನೋ

(5) ಕಂಡಿಕೆ (1) ರಿಂದ (3) ರವರೆಗಿನ ಸಿ.ಡಿ.ಪಿ (ತುಲಪೈ) ರವರ ವರದಿಯನ್ನು ಪರಿಶೀಲಿಸಿದಾಗ, ಕಂಡಿಕೆ (2) ರಲ್ಲಿನ ವಿವರಣೆಗಳಿಗೆ ವರಗಳು ವರದಿಯಲ್ಲಿ ಲಭ್ಯವಿಲ್ಲದ ಕಾರಣ ಮಿಲಾ ಕಛೇರಿಯ ವರಗಳನ್ನು ಕ್ರೋಢೀಕರಿಸಿ ಸಲ್ಲಿಸಲು ಸೂಚಿಸಲಾಗಿದೆ. ಸದರಿ ಮಿಲಾ ಕಛೇರಿಯನ್ನು ಅನುಮೋದನೆಗಾಗಿ ರವಾನಿಸಿ ಸಲ್ಲಿಸಲು ಕೋರಿದೆ.

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಮಹಾಲಕ್ಷ್ಮಿ ಲೇಔಟ್ ವಿಭಾಗ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

(6) CE(W) JA/AM/14

ಮಾಹಿತಿಗಾಗಿ:

(7) ಕಂಡಿಕೆ (1) ರಿಂದ (5) ರ ವರೆಗಿನ ವಿಷಯವನ್ನು ಪರಿಶೀಲಿಸಲು ಕೋರಿದೆ ಅಭಿಪ್ರಾಯಕ್ಕಾಗಿ ಸಲ್ಲಿಸಿದೆ. ಕಂಡಿಕೆ (2) ರಲ್ಲಿ ಸಲ್ಲಿಸಿರುವಂತೆ ಈ ಸಂಸ್ಥೆಯು ಸಲ್ಲಿಸಿರುವ ಪ್ರಸ್ತಾವನೆಯಲ್ಲಿ ಅಳವಡಿಸಿರುವ "DATA RATE" ಪ್ರಸ್ತಾವನೆಯನ್ನು ಪರಿಶೀಲಿಸಿ ಅಭಿಪ್ರಾಯವನ್ನು ತಿಳಿಸಲು ಕೋರಿದೆ. ಈ ಸಂಸ್ಥೆಯ ಪ್ರಸ್ತಾವನೆಯ ಬಗ್ಗೆ ಯಾವುದೇ ಅಭಿಪ್ರಾಯವನ್ನು ಇದುವರೆಗೂ ನೀಡಿರುವುದಿಲ್ಲ. ಆದ್ದರಿಂದ ಈ ಸಂಸ್ಥೆಯ ಪ್ರಸ್ತಾವನೆಯನ್ನು ಪರಿಶೀಲಿಸಿ ಅಭಿಪ್ರಾಯವನ್ನು ತಿಳಿಸಲು ಕೋರಿದೆ.

(8) ಅನು-ಶ (ಆಡಳಿತ)

ಮುಖ್ಯ ಅಭಿಯಂತರರು (ಪಶ್ಚಿಮ)
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಬೆಂಗಳೂರು

(9) SE(W)

Executive Engineer (West)
No. 111/16-17

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಟಿಪ್ಪಣಿ ಹಾಳೆ

ವಿಷಯ : ..... ಪುಟದ ಸಂಖ್ಯೆ .....

..... ಕಡತದ ಸಂಖ್ಯೆ .....

ಪಂಕ್ತಿಯ ಸಂಖ್ಯೆ	ಟಿಪ್ಪಣಿಗಳು ಮತ್ತು ಆಜ್ಞೆಗಳು
(16)	ಸೆಳೆತ ರೇಖೆ FOR providing and laying precast drain cover slabs of 250 mm thickness using M20 concrete for drains ಗೆ ಕೈಗಾರಿಕಾ ಲೇಔಟ್‌ಗಳಲ್ಲಿ ಕೈಯಿಂದಲೂ ಮಾಡಲಾಗದ ಅಥವಾ ಬೇರೆ ರೀತಿಯಲ್ಲಿ ಸಿದ್ಧವಿರುವ ದರಗಳನ್ನು ಅಂತಿಮಗೊಳಿಸಿದ್ದು, ಸದರಿ ಬೆಂಗಳೂರನ್ನು ಬಳಸಲು Data Rate ನ್ನು ಈ ಕಛೇರಿಯ/ಮುಖ್ಯ ಎಂಜಿನಿಯರ ಅನುಮತಿಯ ಬಗ್ಗೆ ಕಡತ ಕೋರಿದೆ ಸಲ್ಲಿಸಿದೆ. 23/8/16
(17)	6.6 (ತತ್ವವು) ಅನುಮೋದಿಸಿದೆ ಮಾಡಿದೆ 23/8/16

DM

EE 1/2

BRUHAT BANGALORE MAHANAGARA PALIKE

Mahalakshmipura Division

Sl. No.	Description of Work	Unit	No.	L m	B m	D m	Quantity	Final Rate Rs	Total Amount Rs
	DATA RATE for Laying Precast Drain Cover Slabs = 250mm thick								
	Providing and Laying Precast Drain Cover Slabs of 250mm thickness for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc., complete and as per drawing and the directions engineer in charge (**size 1.8 X 0.6 X 0.25 m)**								
1	KSRB 4.2.2 : Providing and laying in position **reinforced cement concrete of design mix M20** with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.459cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., ncluding cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 **(Item No. 4.11, Page No. 13 of KPWD S.R 2015-16)**	cum	1	1.8	0.60	0.25	0.270	6347.16	1714.00
2	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness , ncluding attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (Page No 15., I.No.4.31 of KPWD S.R 2015-16).	Sqm	2	1.8	0.25		0.90		
			2	0.6	0.25		0.30		
		Sqm					1.20	306.72	368.06
3	KSRB 4-6.3 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specification. Specification No. KBS 4.6.2 (Page No 15., I.No.4.30 of KPWD S.R 2015-16).	Sqm	1	1.8	0.60		1.08	403.92	436.00
4	KSRB 4.9.2 : Providing T .M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 for TMT Bars Fe500 (Page No 17., I.No.4.46.2 of KPWD S.R 2015-16).								
	Steel 16mm dia - Main Rod @ 150mm c/c		2	5	2.20		22.00		
	Lifting Hook 10mm dia - 2 Nos		1	2	0.30		0.60		
	Total						22.60		
	Total @ 1.58 kg/m						0.04		
	Steel 8mm dia - Distribution Rod @ 150mm c/c		2	13	0.60		15.60		
	Total @ 0.39 kg/m						0.006		
	Total Steel Cost	q						69805.80	2917.00
5	Refixing stone slabs / RCC Precast slabs of drains and pointing in C.M (1:3) (Page No 25., I.No.5.33 of KPWD S.R 2015-16).								
		sqm	1	1.80	0.60		1.08	78.84	85.00
	Rate per each								5520.06
	Rate per Sqm								5111.00

Arpitha.C.P
Asst Engineer

Asst.Executive Engineer

Executive Engineer

"DATA RATE APPROVED" FOR Rupees 5111=00 (Thousand one hundr